

Subdivisions, T. 2 N., R. 34 E.

Chains	
	<p>for cor. to secs. 4, 5, 8 and 9, marked with 5 notches on S and 4 notches on E edges and raised mound of stone over it. Pits impracticable.</p> <p>Land, rolling.</p> <p>Soil, generally 1st rate. Partly under cultivation.</p>
	<p>East on ran. bet. secs. 4 & 9.</p> <p style="text-align: right;">Var. 20°50' East.</p> <p>Set temporary cors. at 20, 40, and 60 chs. and at</p>
79.25	<p>Intersect N & S line 20 lks N of cor. to secs. 3, 4, 9 & 10.</p> <p style="text-align: center;">Thence</p> <p>N. 89° 51' W. on true line.</p> <p style="text-align: right;">Var. 19½° East.</p>
8.50	Enter river bottom.
9.50	Gravel bed of old channel.
19.81	<p>Set boulder 16 x 14 x 12 ins. 10 ins. in ground for 1/16 sec. cor., marked 1/16 on N face and raised mound of boulders over it. Pits impracticable.</p>
25.00	Leave river and old bed N.W.
26.00	Bluff rock
	Descend gradually.
39.63	<p>Deposited charred stake 12 ins. in the ground for ¼ sec. cor.; dug pits 18 x 18 x 12 ins. E & W. of stake, 5½ ft. dist.; raised mound of gravel and earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked ¼ S on N. face.</p>
43.60	Old mill race S.W. dry.
44.50	Enter river bottom.
59.44	<p>Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E & W of cor. 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N. face, from which</p>

+50

-10