

Subdivisions, T. 2 N., R. 34 E.

Chains		
	Old Grist Mill bears S.W. about 5 chains.	
74.50	Tail race N.W.	-10
79.25	Cor. to secs. 4, 5, 8 and 9.	
	Land, somewhat broken and rough.	
	Soil, 1st rate in bottom. Part of this land can be cultivated. Some good bunch grass.	
	North bet. secs. 4 and 5.	
	Var. 20° 50' East	
3.40	Tail race N.W.	
6.50	O.R. & N. Railway E & W.	+10
13.70	Wagon road E & W.	
24.30	Umatilla River 180 lks. wide runs West.	
27.00	Leave river bottom and begin ascent.	
40.00	Set basalt stone 10 x 8 x 7 ins., 7 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face; dug pits 18 x 18 x 12 ins. N & S of stone $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
43.00	Wagon road E & W.	+200
60.00	Deposited charred stake, 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on W. face.	
74:60	Intersect Tp. line 8.00 chains E. of cor. to secs. 32 & 33 T. 3 N R 34 East and set post 4 ft. long, 4 ins. square, 24 ins. in the ground for closing cor. to secs. 4 and 5, marked C.C. T. 2 N.R. 34 E. on S; S.4 on E. and S.5 on W. face, with 4 notches on E and 2 notches on W. faces; dug pits 18 x 18 x 12 ins. S. E. and W. of post $5\frac{1}{2}$ ft. dist. and raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it.	+400
	Land, rolling. Soil, 2nd rate and rocky. Timber, cotton-wood and willow in river bottom. Some bunch grass.	