

Subdivisions, T. 2 N., R. 34 E.

Chains		
	North bet. secs. 31 and 32.	
		Var. 20° East.
9.60	Canyon N.W.	-50
	Ascend.	
39.00	Top ridge N.W.	+300
40.00	Set basalt stone 16 x 16 x 8 ins., 10 ins. in the ground for $\frac{1}{4}$ sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stone $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
	Descend.	
77.50	Canyon N.W.	-300
	Ascend steep hill.	
80.00	Set basalt stone 14 x 12 x 10 ins., 9 ins. in the ground for cor. to secs. 29, 30, 31 and 32, marked with 1 notch on S. and 5 notches on E. edges and raised mound of stone over it. Pits impracticable.	
	Land, rough and mountainous 80. chs.	
	Soil, 2nd rate and rocky. Fine bunch grass.	
<hr/>		
	East on ran. bet secs. 29 & 32.	
		Var. 21° East.
40.00	Set temporary $\frac{1}{4}$ sec. cor. and at	
80.00	Intersect N & S line 40 lks. S. of cor. to secs. 28, 29, 32 & 33,	
	Thence	
	S. 89° 43' W. on true line.	
		Var. 18° East.
13.00	Head of canyon N.	-20
24.00	Wagon road N.W.	
30.00	Summit ridge.	+150
40.00	Set basalt stone 12 x 9 x 7 ins., 8 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face; dug pits 18x18x12 ins. E & W. of stone $5\frac{1}{2}$ ft. dist., and raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
	Descend gradual slope.	