

Subdivisions, T. 2 N., R. 34 E.

Chains	West on ran. bet. secs. 19 & 30.	
	Var. 21° East.	
84.35	Set temporary cors. at 20, 40 & 60 chains and at Intersect Tp. line 50 lks. N. of cor. to secs. 24, 25, 19 & 30.	
	Thence,	
.75	North 89° 40' E. on true line. Brook 6 lks., course N.	Var. 17°25' East.
10.00	Summit N.	+400
	Descend.	
24.35	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face and raised mound of stone over it. Pits impracticable.	
37.50	Canyon, N.	-400
44.35	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/4 sec. cor., marked 1/4 on N. face; raised mound of stone alongside. Pits impracticable.	
64.35	Set basalt stone 10 x 9 x 8 ins., 6 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face ; dug pits 18 x 18 x 12 ins. E. & W. of stone 5 1/2 ft. dist. and raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.	
74.90	Canyon N.W.	-200
	Ascend.	
84.35	Cor. to secs. 19, 20, 29 & 30. Land, rough and mountainous 84.35 chs. Soil, 1st rate. Can partly be cultivated. Grass, good.	
	North bet. secs. 19 & 20.	
	Var. 21° East.	
	Descend gradual slope.	
20.00	Set stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/16 sec. cor., marked 1/16 on W. face; dug pits 18x18x12 ins., N & S. of cor. 5 1/2 ft. dist. and raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.	
23.30	Gulch N.W.	-100
40.00	Set stone 12 x 10 x 8 ins., 8 ins. in the ground for 1/4 sec. cor. marked 1/4 on W. face and raised a mound of stone over it. Pits impracticable.	