

Subdivisions, T. 2 N., R. 34 E.

Chains		
45.00	Top of hill, N.W. Descend gradual slope.	‡50
60.00	Set basalt stone 12 x 12 x 12 ins., 8 ins. in the ground for 1/16 sec. corner, marked 1/16 on W. face; raised mound of stone over it. Pits impracticable.	
62.00	Dry ditch W.	
80.00	Set basalt stone 12 x 10 x 8 ins., 8 ins. in the ground for corner to secs. 17, 18, 19 and 20, marked with 3 notches on S. and 5 notches on E. edges and raised md. of stone 2 ft. high, 4½ ft. base over it. Land, mostly rolling hills. Soil, 4th rate and rocky. Some bunch grass. Some of land west of line can be cultivated.	
	East on random bet. secs. 17 & 20. Var. 19° East. Set temporary cors. at 20, 40 and 60 chains and at	
79.25	Intersect E. bdy. at corner to secs. 16, 17, 20 and 21. Thence, West on true line. Var. same.	
19.81	Set basalt stone 10 x 8 x 7 ins., 6 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face; dug pits 18 x 18 x 12 ins. E & W of stone, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it.	
34.75	Gulch N.	-20
39.62	Set stone 12 x 8 x 7 ins., 8 ins. in the ground for ¼ sec. cor., marked ¼ on N. face; dug pits 18 x 18 x 12 ins. E & W of stone, 5½ ft. dist., and raised mound of earth 1½ ft. high, 3½ ft. base over it.	
56.50	Gulch, N.	-50
59.43	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. East & W. of stake 5½ ft. dist.; raised mound of stone and earth 1½ ft. high, 3½ ft. base over it, and in East pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked 1/16 on N. face.	