

Subdivisions, T. 2 N., R. 34 E.

Chains	
	over it and in N. pit drove charred stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on W. face.
25.35	Gulch N.W.
40.00	Deposited charred stake 12' ins. in the ground for $\frac{1}{4}$ sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked $\frac{1}{4}$ S on W. face.
51.80	Wagon road E & W.
60.00	Drove charred stake 12' ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake, 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it and in N pit drove stake 2 ft. long, 2 ins. square, 12' ins. in the ground marked 1/16 S on W. face.
80.00	Deposited charred stake 12 ins. in the ground for cor. to secs. 7, 8, 17 & 18; dug pits 18x18x12 ins. in each sec. 5 $\frac{1}{2}$ ft. dist.; raised mound of earth 2 ft. high, 4 $\frac{1}{2}$ ft. base over it and in S. E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground, marked T 2 N S 8 on N E.; R 34 E S 17 on S.E.; S 18 on S W and S 7 on N W faces with 4 notches on S and 5 notches on E edges. Land, rolling, well adapted for agriculture. Soil, 1st rate. Fine grass.
	East on random bet. secs. 8 & 17. Var. 20° East. Set temporary cors. at 20, 40 and 60 chains and at
79.75	Intersect N & S line 45 lks. N of cor. to secs. 8, 9, 16 & 17. Thence N. 89° 41' W. on true line. Var. 21-3/4° East.
9.85	Dry ditch N.W.
15.75	Leave field.
19.94	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground