

Subdivisions, T. 2 N. R., 34 E.

Chains	for 1/16 sec. cor. and marked 1/16 on N. face; raised mound of stone over it. Pits impracticable.
39.88	Set basalt stone 10 x 10 x 10 ins., 7 ins. in the ground for $\frac{1}{4}$ sec. cor. and marked $\frac{1}{4}$ on N. face; dug pits 18 x 18 x 12 ins. E & W of stone $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
58.19	Gulch, N.W.
59.82	Set basalt stone 10 x 8 x 8 ins., 6 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face; dug pits 18 x 18 x 12 ins. E & W of stone $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
79.75	Cor. to secs. 7, 8, 17 and 18. Land, rolling. Soil, 1st rate. Partly cultivated.
	West on random bet. secs. 7 & 18. Var. 20° East. Set temporary $\frac{1}{4}$ and 1/16 sec. cors. at 20, 40 and 60 chains and at
83.90	Intersect Tp. line 21 lks. N. of cor. to secs. 12, 13, 7 & 18. Thence N. 89° 51' East on true line. Var. 20-3/4° East.
23.65	Enter field N & S.
23.90	Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/16 sec. cor., marked 1/16 on N. face; dug pits 18 x 18 x 12 ins. E & W of stone $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.
38.15	Leave field N & S.
43.90	Set basalt stone 14 x 10 x 6 ins., 10 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face; raised mound of stone over it. Pits impracticable.
59.50	Wagon road N & S.
63.90	Deposited charred stake 12 ins. in the ground for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. E & W of stake,