

Subdivisions, T. 2 N. R. 34 E.

Chains		
	<p>5½ ft. dist.; raised mound of stone and earth 1½ ft. high, 3½ ft. base over it and in E. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked 1/16 S on N face.</p>	
83.90	<p>Cor. to secs. 7, 8, 17 & 18. Land, rolling. Soil, 1st rate. Partly cultivated.</p>	
	<p>North bet. secs. 7 & 8.</p>	
	<p style="text-align: right;">Var. 20° East.</p>	
20.00	<p>Set basalt stone 12 x 8 x 7 ins., 8 ins. in the ground, marked 1/16 on W. face for 1/16 sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stone 5½ ft. dist.; raised mound of earth, 1½ ft. high, 3½ ft. base over it.</p>	
40.00	<p>Set basalt stone 12 x 8 x 7 ins., 8 ins. in the ground for ¼ sec. cor., marked ¼ on W. face; dug pits 18x18x12 ins. N & S of stone, 5½ ft. dist.; raised mound of earth 1½ ft. high, 3½ ft. base over it.</p>	
51.80	<p>Dry bed of creek N.W.</p>	-50
60.00	<p>Set basalt stone 14 x 10 x 8 ins., 10 ins. in the ground for 1/16 sec. cor. marked 1/16 on W. face; dug pits 18 x 18 x 12 ins. N and S of stone 5½ ft. dist. and raised mound of earth 1½ ft. high, 3½ ft. base over it.</p>	
63.30	<p>O.R. & N. Railway.</p>	+10
80.00	<p>Set basalt stone 14 x 12 x 7 ins., 10 ins. in the ground for cor. to secs. 5, 6, 7 and 8, marked with 5 notches on S and E edges and raised mound of stone 2 ft. high, 4½ ft. base over it. Pits impracticable. Land, mostly rolling hills. Soil, 1st rate except in river bottom which is very gravelly. No grass. Mostly good for agriculture. No timber or water.</p>	
	<p>East on random bet. secs. 5 and 8.</p>	
	<p style="text-align: right;">Var. 20° 50' East</p>	