

Subdivisions, T. 2 N., R. 34 E.

Chains

- 22.50 Umatilla river 90 lks. runs. W.
- 40.00 Deposited charred stake 12 ins. in the ground for $\frac{1}{4}$ sec. cor.; dug pits 18 x 18 x 12 ins. N & S of stake, $5\frac{1}{2}$ ft. dist.; raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it and in N. pit drove stake 2 ft. long, 2 ins. square, 12 ins. in the ground marked $\frac{1}{4}$ S on W. face.
- 43.00 Wagon road S.E.
- 60.00 Set basalt stone 16 x 10 x 8 ins., 10 ins. in the ground for $\frac{1}{16}$ sec. cor., marked $\frac{1}{16}$ on W. face and raised mound of stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. Pits impracticable.
- 75.20 Intersect Tp. line 810 lks. E. of cor. to secs. 31 & 32, T. 3 N R 34 E and deposited charred stake 12 ins. in the ground for closing cor. to secs. 5 & 6; dug pits 18 x 18 x 12 ins. S. E. & W. of stake $5\frac{1}{2}$ ft. dist.; raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base over it and in the E. pit drove stake 2 ft. long, 2 ins. square 12 ins. in the ground, marked: C.C. T2 N R 34 E on S; S 5 on E and S 6 on W faces, with 5 notches on E and 1 notch on W. edges.

Land, mostly high and rolling.

Soil, 1st & 2nd rate.

Timber, balm and thorns in river bottom. No grass.

Sept. 6th, 1887.

General Description

The South half of this Township and a small part of the North half is rough and mountainous. The soil varying from 3d to 4th rate with fair bunch grass with scattering timber over most of it. The remainder of the Township is generally rolling land, well adapted for agriculture, containing good grass and balm timber along the Umatilla River bottom. Soil, 1st rate. It also contains several improved fields and dwelling houses.