

Field Notes of the survey for topography
 Lines of T. 2 N., R. 34 E., by Currin and
 Noland, under their special contract,
 Dated May 4th, 1887.

Chains	<p>Line between sections 3 and 4.</p> <p>From corner sections 3, 4, 9 & 10, a charred stake with pits in each section, $5\frac{1}{2}$ ft. distant, mound over it.</p> <p>North between sections 3 and 4.</p> <p style="text-align: right;">Var. $19\frac{1}{2}^{\circ}$ East.</p>
2.20	Umatilla River, 150 links, course West.
10.00	Leave river bottom.
12.50	O. R. & N. R. R. Course E & W.
17.00	Road, course S. W., stops at station.
40.00	$\frac{1}{4}$ sec. corner. Post marked $\frac{1}{4}$ on W. face. Pits North and South $5\frac{1}{2}$ feet distant.
43.80	Wagon road, course N. W. & S. E.
	<p>North on line bet. secs. 5 & 6.</p> <p style="text-align: right;">Var. $20^{\circ}50'$ East.</p> <p>From corner sections 5, 6, 7 and 8, a stone 14 x 12 x 7 ins. in stone mound.</p>
12.50	Umatilla River, 90 links, runs West.
	<p>Line between sections 9 and 16.</p> <p>From corner sections 9, 10, 15 and 16, a basalt stone 18 x 12 x 8 ins., with 4 notches on S. and 3 on E. edges; pits in each section $5\frac{1}{2}$ feet distant.</p> <p>West between secs. 9 & 16.</p> <p style="text-align: right;">Var. $21-3/4^{\circ}$ East.</p>
19.87	Pass the 1/16 sec. corner and at
30.25	Dry gulch, course N.
	<p>Line between secs. 22 & 23.</p> <p>From corner sections 22, 23, 26 and 27, a stone 12 x 10 x 8 ins. Pits in each section. Stone marked with 2 notches on the East and South edges.</p>