

Exterior Lines of T. 3 N., R. 35 E.
 Surveyed by William H. Odell under contract No. 114.
 Dated July 2, 1866.

(South Boundary)

Chains		
	East on South boundary of section 31. Var. 21°30' East.	
40.00	Set $\frac{1}{4}$ section post corner on hillside facing West, drove charred stake, and made stone mound as per instructions.	-30
64.50	Right bank of Umatilla River, 150 wide, course S.W.	-150
67.00	Enter timber.	
80.00	To corner for sections 31, 32, 5 and 6, in edge of Umatilla River, course N.W., from which, A pine, 20 ins. diam., bears East 1.15 chs. on right bank of River, also A pine, 8 ins. diam., bears N.45°E., 75 lks. Land, broken on this line, hillsides stony. Timber, along the banks of the river consist of balm, alder and a few pines. Undergrowth the same. The land along river bottom, rich but gravelly.	
	East on South boundary of section 32. Var. 20° East.	
23.50	Edge of Umatilla River. Thence along the channel of the river.	
30.00	Leave river to the right.	
40.00	Made corner for $\frac{1}{4}$ section on pine, 3 ins. diam., from which, A pine, 30 ins. diam., bears S.78°W., 1.50 lks. " " 6 " " " N.56°W., 50 lks.	
45.00	Leave timber and pass over point of hill.	
73.00	Stage Road from Boise City to Umatilla River, course N. and S. Stage station bears South about 3.00.	
80.00	Set post corner for sections 32, 33, 4 and 5, drove charred stake. Dug pits as per instructions. Land, broken and rocky. Timber, balm, pine and alder. Undergrowth the same.	
	East on South boundary of section 33. Var. 20° East.	
38.00	Var. 18°30' East.	+150