

South Boundary of T. 3 N., R. 35 E.

Chains	East on South boundary of section 36. Var. 21° East.	
15.00	Small creek, 15 lks. wide, course North. Narrow belt of balm and pine timber along banks.	-75
40.00	Set post corner for $\frac{1}{4}$ section, deposited marked stone. Dug pits and raised mound as per instructions.	†150
80.00	Set post corner for Townships 2 and 3 North, Ranges 35 and 36 East, sections 1, 6, 31 and 36. Drove charred stake, dug pits, and raised mound as per instructions. Corner on hillside facing the North West. Land, broken and rocky. Good grass.	
Exterior Line of T. 3 N., R. 35 E. Surveyed by Zenas F. Moody under contract No. 164. Dated October 4, 1871. (South Boundary)		
Begin at the established corner to Tps. 2 and 3 North, Ranges 34 and 35 East. East on South boundary of sec. 31. Var. 22° E.		
40.00	Set stone, 17x15x9, for $\frac{1}{4}$ sec. cor., facing West.	
67.40	Enter timber.	
80.00	Set post for cor. to sections 31, 32, 5 and 6 in edges of Umatilla River. The land along this line is hilly. Soil, stony. Good grass.	
East on South boundary of sec. 32. Var. 20°30' East.		
24.00	Edge of Umatilla River.	
40.00	Set post and made mound of stone for $\frac{1}{4}$ sec. cor.	
46.00	Leave timber and pass over foothills.	
71.50	Stage Road, course N. and S.	
80.00	Set post and made stone mound for cor. to secs. 32, 33, 4 and 5.	