

## East Boundary of T 2 N., R. 35 E.

Chains	for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Raised mound of stone alongside. Pits impracticable.	
70.00	Gulch, course E.	-350
80.00	Set a basalt stone, 9x8x7 ins., 6 ins. in the ground, for cor. to secs. 19, 24, 25 and 30, marked 2 notches on S. and 4 on N. edges. Raised a mound of stone alongside. Pits impracticable.	
	Land, mountainous. 80 chs.	
	Soil, 4th rate.	
	No timber. Good bunch grass.	
North on E. bdy. of sec. 24.		
	Var. 21°E.	
3.00	Top of ridge.	+1000
20.00	Canyon, course N.E.	-400
38.00	Top of ridge.	+400
40.00	Set a basalt stone, 14x8x6 ins., 9 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Raised md. of stone alongside. Pits impracticable.	
45.00	Gulch, course S.E.	-250
57.50	Top of ridge.	+250
80.00	Set a basalt stone, 12x9x7 ins., 8 ins. in the ground, for cor. to secs. 13, 18, 19 and 24, marked 3 notches on N. and S. edges. Raised mound of stone alongside. Pits impracticable.	
	Land, mountainous. 80 chs.	
	Soil, rocky, 4th rate.	
	No timber. Good grass.	
North on E. bdy. sec. 13.		
	Var. 21°E.	
18.00	Top of ridge, course E.	+300
37.50	Canyon, course E.	-700
40.00	Set a basalt stone, 10x8x7 ins., 7 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face. Raised a md. of stone alongside. Pits impracticable.	