

South Boundary of T. 3 N., R. 35 E.

Chains	<p>5 notches on W. edges. Raised a mound of stone over it. †200 Pits impracticable.</p> <p>Land, mountainous. 80 chs. Soil, 3rd rate. Pine and balm timber along creek. Good bunch grass on ridges.</p>	
	<p>South 89°50'W. on S. bdy. sec. 35. Var. 23°E.</p>	
20.00	Summit of ridge.	†300
40.00	Set a basalt stone, 12x10x5 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face. Raised mound of stone over it. Pits impracticable.	
68.80	Enter pasture. Fence runs N.E. and S.W.	
80.00	Set a post, 48x4x4 ins., 24 ins. in the ground, for cor. to secs. 34 and 35, marked T 3 N S 34 on N.W., R 35 E S 35 on N.E., T 2 N on S., with 2 notches on E. and 4 notches on W. edges. Dug pits, 18x18x12 ins., N. E. and W. of post, 5 $\frac{1}{2}$ ft. dist., raised a mound of earth and stone, 2 ft. high, 4 $\frac{1}{2}$ ft. base around post. Land, mountainous. 80.00 chs. Soil, 2nd rate. Small scattering pine and good bunch grass.	
	<p>South 89°50'W. on S. bdy. sec. 34. Var. 19°E.</p>	
16.40	Descend bluff to river bottom.	-50
21.80	Wagon road, course S.W. and N.E.	
24.80	O.R. and N.R.R. track, course S.80°W.	
40.00	Set a basalt stone, 12x10x10 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face, raised stone mound over it. Pits impracticable.	
54.40	Umatilla River, 200 lks. wide, course S.W. Leave bottom.	
73.15	Gulch, course S.	
80.00	Set a basalt stone, 12x10x8 ins., 8 ins. in the ground,	