

South Boundary of T. 3 N., R. 35 E.

Chains		
	for cor. to secs. 33 and 34, marked 3 notches on E. and W. edges. Raised a mound of stone over it. Pits impracticable.	+150
	Land, mountainous. 16.40 chs.	
	Soil, gravelly in bottom, 4th rate.	
	Heavy brush; pine and balm timber in bottom. 63.60 chs.	
<hr/>		
	South 89°50'W. on S. bdy. sec. 33.	
	Var. 18°E.	
11.60	Head of gulch, course S.	-60
40.00	Set a basalt stone, 14x10x6 ins., 9 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face. Raised mound of stone over it. Pits impracticable.	+200
61.40	Summit of ridge.	+100
68.40	Spring branch, 2 lks. wide, course S.	-100
80.00	Set a basalt stone, 12x10x8 ins., 8 ins. in the ground, for cor. to secs. 32 and 33 marked 4 notches on E. and 2 notches on W. edges. Dug pits, 18x18x12 ins., N. E. and W. of cor., $5\frac{1}{2}$ ft. dist., raised mound of earth 2 ft. high, $4\frac{1}{2}$ ft. base alongside.	-200
	Land, mountainous. 80.00 chs.	
	Soil, rocky, 4th rate.	
	Poor grass. No timber.	
<hr/>		
	South 89°50'W. on S. bdy. sec. 32.	
	Var. 22°15'E.	
3.40	Wagon road, course N.W. and S.E. Enter bottom.	
12.50	Umatilla river, 120 lks. wide, course N.80°W.	
19.50	Umatilla River, 120 lks. wide, course S.70°W.	
40.00	A pine, 7 ins. diam., which I marked $\frac{1}{4}$ S on N. face, for $\frac{1}{4}$ sec. cor. Raised mound of stone alongside. Pits impracticable.	
48.50	Umatilla River, 75 lks. wide, course N.W.	
68.00	Umatilla River, 50 lks. wide, course S.W.	
78.50	Umatilla River, 80 lks. wide, course N.W.	