

Subdivision of T. 2 N., R. 35 E.
 Surveyed by Currin and Noland, special contract.
 Dated May 4, 1887.

Chains	From the corner to secs. 1, 2, 35 and 36 on the S. bdy. of the Township previously established by me under this contract I run	
	North on true line between secs. 35 and 36. Var. 25° East.	
20.00	Summit of ridge, course W.	+300
40.00	Set a basalt stone, 12x10x8 ins., 8 ins. in the ground, for $\frac{1}{2}$ sec. cor. marked $\frac{1}{2}$ on W. face, over which I erected a mound of stone, 18 ins. high, with $3\frac{1}{2}$ ft. base.	
45.00	Canyon, course S.W.	-400
62.50	Summit of table land.	+400
80.00	Set basalt stone, 18x10x10 ins., 12 ins. in the ground, for cor. to 25, 26, 35 and 36 marked with 1 notch on E. and S. edges over which I raised a mound of stone 2 ft. high with $4\frac{1}{2}$ ft. base.	
	Land, mountainous. No timber. 80 chs.	
	Good grass.	
	Soil, 2nd rate.	
	East on true line between secs. 25 and 36. Var. 22° East.	
7.50	Head of canyon, course N.	-50
25.00	Summit of ridge, course N.	+75
40.00	Set basalt stone, 12x12x6 ins., 8 ins. in the ground, for $\frac{1}{2}$ sec. cor. marked $\frac{1}{2}$ on N. face, over which I raised a mound of stone 18 ins. high with $3\frac{1}{2}$ ft. base.	
46.75	Canyon, course N.W.	-200
69.50	Summit of ridge, course N.W.	+30
80.00	Intersect Township, 3.50 chs. S. of cor. to secs. 30 and 31, T 2 N R 36 East and set a stone, 8x10x12 ins., 8 ins. in the ground, for closing cor. to 25 and 36 marked C C on W. face, with 1 notch on S. and 5 on N. edges, over which I raised a mound of stone 2 ft. high with $4\frac{1}{2}$ ft. base.	