

Subdivisions of T. 2 N., R. 35 E.

Chains	<p>Land, rough and mountainous. 80 chs. Pine timber in canyon. Good grass. Soil, 2nd rate.</p>	C
	<p>North on true line between secs. 25 and 26. Var. 22° East.</p>	
25.00	Begin to descend.	
35.60	Canyon, course N.E.	-200
40.00	<p>Set stone, 12x12x6 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face over which I raised a mound of stone, 18 ins. high with $3\frac{1}{2}$ ft. base.</p>	
60.00	Gulch, course N.W.	-150
72.00	Top of ridge.	
80.00	<p>Set basalt stone, 9x8x7 ins., 6 ins. in the ground, for cor. to secs. 23, 24, 25 and 26 marked with 2 notches on S. and 1 on E. edges, over which I raised a mound of stone, 2 ft. high with $4\frac{1}{2}$ ft. base.</p>	
	<p>Good bunch grass. Soil, 4th rate and rocky. Land, rough and mountainous. 80 chs.</p>	
	<p>East on true line between secs. 24 and 25. Var. 20° East.</p>	
20.75	Canyon and dry bed of creek.	
40.00	<p>Set stone, 7x8x9 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face over which raised a mound of stone, 18 ins. high with $3\frac{1}{2}$ ft. base.</p>	
47.50	Top of ridge, course N.W.	
55.00	Small gulch, course N.W.	-100
63.00	Top of ridge, course N.	+200
80.00	<p>Intersect Township line 3.50 chs. S. of cor. to secs. 19 and 30, T. 2 N. R. 36 E. and set basalt stone, 7x8x9 ins., 6 ins. in the ground, for closing cor. to secs. 24 and 35, marked C C on W. face with 2 notches on S. and 4 on N. edges, over which I erected a mound of stone 2 ft.</p>	