

Subdivisions of T. 2 N., R. 35 E.

Chains	<p>Land, very rough and mountainous. 80 chs. Good grass. Soil, 4th rate and rocky.</p> <p style="text-align: right;">September 7, 1887.</p>	
	<p>North on true line between secs. 13 and 14. Var. 22° East.</p> <p>Ascend.</p> <p>40.00 Set a post 3 ft. long and 3 ins. square, 24 ins. in the ground, for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S on W. face, around which I raised a mound of stone, 18 ins. high with $3\frac{1}{2}$ ft. base.</p> <p>45.00 Summit of ridge, course N.W.</p> <p>47.00 Gulch, course N.W.</p> <p>54.00 Top of ridge.</p> <p>62.00 Canyon.</p> <p>80.00 Set a basalt stone, 10x12x14 ins., 10 ins. in the ground, for cor. to secs. 11, 12, 13 and 14 marked with 1 notch on E. and 4 on S. edges, over which I raised a mound of stone 2 ft. high with $4\frac{1}{2}$ ft. base.</p> <p>Land, rough and mountainous. 80 chs. Soil, stony, 4th rate. Bunch grass.</p>	<p style="text-align: right;">+100 -50 +100 -250</p>
	<p>East on true line between secs. 12 and 13. Var. 21° East.</p> <p>20.00 Gulch, course N.W.</p> <p>40.00 Set a stone, 7x8x9 ins., 6 ins. in the ground, for $\frac{1}{2}$ sec. cor. marked $\frac{1}{2}$ on N. face, and raised a mound of stone over it. Pits impracticable.</p> <p>60.00 Top of ridge or divide, course N.</p> <p>79.60 Intersect Township line 3.60 chs. South of cor. to secs. 7 and 18, T. 2 N., R. 36 E. and set a stone, 7x8x9 ins., 6 ins. in the ground, for closing cor. to secs. 12 and 13 marked C C on W. face with 4 notches on S. and 2 on N. edges, and raised a mound of stone 2 ft. high with</p>	<p style="text-align: right;">-400</p>