

Subdivisions of T. 2 N., R. 35 E.

| Chains | From the corner to secs. 2, 3, 34 and 35 on S. bdy. of Township I run | |
|--------|---|-------|
| | North on true line between secs. 34 and 35. | |
| | Var. 27°30' East. | |
| 5.60 | Creek, 20 lks. wide, course N.W. | -100 |
| 8.00 | Ascend and leave creek bottom. | |
| 40.00 | Set a stone, 7x8x9 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, and raised a mound of stone $1\frac{1}{2}$ ft. high, with $3\frac{1}{2}$ ft. base over it. Pits impracticable. | |
| 44.50 | Top of ridge, course W. | +1000 |
| 67.75 | Creek in canyon, course N.W. Ascend. | |
| 80.00 | Set a stone, 10x12x18 ins., 12 ins. in the ground, for cor. to secs. 26, 27, 34 and 35 marked with 2 notches on E. and 1 on S. edges, and raised a mound of stone 2 ft. high with $4\frac{1}{2}$ ft. base over it. Pits impracticable. Land, mountainous. 80 chs. Some grass. Soil, rocky, 4th rate. | |
| | East on random between secs. 26 and 35. | |
| | Var. 19°20' East. | |
| 40.00 | Set temp. $\frac{1}{4}$ sec. cor., and at | |
| 79.50 | Intersect N. and S. line, 68 lks. S. of cor. to secs. 25, 26, 35 and 36. Thence S. 89°31' W. on true line. | |
| 30.00 | Leave table land and descend. | |
| 39.75 | Set a stone, 18x10x9 ins., 12 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone $1\frac{1}{2}$ ft. high, with $3\frac{1}{2}$ ft. base over it. Pits impracticable. | |
| 45.00 | Gulch, course S. Ascend. | -300 |
| 79.50 | To cor. to secs. 26, 27, 34 and 35. Land, broken and mountainous. 79.50 chs. Good grass on bench land. Soil, poor and rocky. | |