

## Subdivisions of T. 2 N., R. 35 E.

|        |  |                         |
|--------|--|-------------------------|
| Chains | <p>E. edges, from which,</p> <p>A pine, 8 ins. diam., bears S.40°E., 39 lks. dist., marked R 35 E S 23 B T; and</p> <p>A pine, 10 ins. diam., bears S.50°W., 60 lks. dist., marked S 22 B T.</p> <p>No other trees within limits.</p> <p>Raised a mound of stone alongside. Pits impracticable.</p> <p>Soil, 4th rate.</p> <p>Timber in canyons.</p> <p>Land, mountainous. 80 chs.</p>   |                         |
|        | <p>East on random between secs. 14 and 23.</p> <p>Var. 22° East.</p> <p>40.00 Set temp. <math>\frac{1}{4}</math> sec. cor., and at</p> <p>80.00 Intersect N. and S. line, 30 lks. S. of cor. to secs. 13, 14, 23 and 24.</p> <p>Thence S.89°47'W. on true line.</p> <p>39.00 Creek, 15 lks. wide, runs N.</p> <p>40.00 A pine, 24 ins. diam., marked <math>\frac{1}{4}</math> S on N. face, for <math>\frac{1}{4}</math> sec. cor., from which,</p> <p>A pine, 24 ins. diam., bears N.50°E., 55 lks. dist., marked <math>\frac{1}{4}</math> S B T; and</p> <p>A pine, 18 ins. diam., bears S.75°E., 50 lks. dist., marked <math>\frac{1}{4}</math> S B T.</p> <p>40.50 Bluff of rock, 16 ft. high.</p> <p>Ascend.</p> <p>80.00 To cor. to secs. 14, 15, 22 and 23.</p> <p>Land, rough and mountainous. 80 chs.</p> <p>Pine timber in canyons. Good grass.</p> <p>Soil, 3rd rate.</p> <p>September 7, 1887.</p> |                         |
|        | <p>North on true line between secs. 14 and 15.</p> <p>Var. 22° East.</p> <p>2.00 Gulch, course N.E.</p> <p>10.00 Canyon, course E.</p>   | <p>-100</p> <p>-250</p> |