

Subdivisions of T. 2 N., R. 35 E.

Chains		
60.00	Ridge, course East.	+500
69.00	Canyon, course East.	-300
80.00	Set a stone, 8x10x12 ins., 8 ins. in the ground, on top of sharp ridge, for cor. to secs. 21, 22, 27 and 28 marked with 3 notches on E. and 2 on S. edges, and raised a mound of stone 2 ft. high with 4½ ft. base over it. Pits impracticable.	
	Land, mountainous. 80 chs.	
	Good grass. Pine and fir timber in canyons.	
	Soil, 3rd rate.	
East on random between secs. 22 and 27.		
Var. 21° East.		
40.00	Set temp. ¼ sec. cor., and at	
79.90	Intersect N. and S. line, 28 lks. S. of cor. to secs. 22, 23, 26 and 27.	
	Thence S. 89° 48' W. on true line.	
20.00	Summit, course South.	+400
36.00	Gulch, course South	-200
39.95	Set stone, 6x8x15 ins., 10 ins. in the ground, for ¼ sec. cor. marked ¼ on N. face, and raised a mound of stone 1½ ft. high with 3½ ft. base over it. Pits impracticable.	
54.35	Gulch, course S.E.	-100
79.90	To cor. to secs. 21, 22, 27 and 28.	+700
	Land, mountainous. 79.90 chs.	
	Good grass.	
	Soil, 1st rate.	
North on true line between secs. 21 and 22.		
Var. 21° East.		
18.00	Canyon, course East.	-400
	Ascend.	
36.00	Summit of ridge, course East.	+400
40.00	Set a stone, 7x8x9 ins., 6 ins. in the ground, for ¼ sec. cor. marked ¼ on W. face, and raised a mound of stone 1½ ft. high with 3½ ft. base over it. Pits impracticable.	