

## Subdivisions of T. 2 N., R. 35 E.

Chains		
40.00	Set a stone, 7x8x9 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
56.00	Gulch, course N.W.	
68.00	Top of ridge, N.W. Descend.	+300
80.00	Set a stone, 7x8x9 ins., 6 ins. in the ground, for cor. to secs. 3, 4, 9 and 10 marked with 4 notches on S. and 3 on E. edges, and raised a mound of stone 2 ft. high with $4\frac{1}{2}$ ft. base over it. Pits impracticable. Land, rough and mountainous. 80 chs. Bunch grass. Soil, 3rd rate.	
East on random between secs. 3 and 10. Var. 20° East.		
40.00	Set temp. $\frac{1}{4}$ sec. cor., and at	
80.40	Intersect N. and S. line at cor. to secs. 2, 3, 10 and 11. Thence West on true line.	
5.50	Gulch, course N.	-20
13.75	Gulch, course N.	-40
30.00	Canyon, course N.	-50
40.20	Set a stone, 8x10x12 ins., 8 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
71.00	Top of ridge.	+300
77.50	Gulch or canyon.	-250
80.40	To cor. to secs. 3, 4, 9 and 10. Land, rough and mountainous. 80.40 chs. Soil, 3rd rate. Bunch grass.	