

Subdivisions of T. 2 N., R. 35 E.

Chains	Raised a mound of stone alongside.	
57.00	Wagon Road or old Stage road.	
78.75	Canyon, course W.	-100
80.00	Set a stone, 7x10x12 ins., 8 ins. in the ground, for cor. to secs. 28, 29, 32 and 33 marked with 4 notches on E. and 1 on S. edges, and raised a mound of stone 2 ft. high with 4½ ft. base over it. Pits impracticable.	
	Land, rolling.	
	Soil, 2nd rate.	
	Some pine timber. Good grass.	
	September 8, 1887.	
	East on random between secs. 28 and 33.	
	Var. 19° East.	
40.00	Set temp. ¼ sec. cor., and at	
80.00	Intersect N. and S. line, 25 lks. N. of cor. to secs. 27, 28, 33 and 34.	
	Thence N.89°49'W. on true line.	
5.00	Top of ridge, slopes S.E.	+200
11.00	Gulch, dry.	-100
30.00	Top of ridge, course S.E.	+600
37.00	Canyon.	-100
40.00	Set a stone, 6x8x12 ins., 8 ins. in the ground, for ¼ sec. cor. marked ¼ on N. face, and raised a mound of stone 1½ ft. high with 3½ ft. base over it. Pits impracticable.	
55.00	Top of mountain.	+1200
62.75	Old Stage road, course S.	
80.00	To cor. to secs. 28, 29, 32 and 33.	
	Land, high and mountainous. 80 chs.	
	Scattering pines. Some grass.	
	Soil, 2nd rate.	
	North on true line between secs. 28 and 29.	
	Var. 19° East.	
27.00	Top of hill, course N.E.	+600