

Subdivisions of T. 2 N., R. 35 E.

Chains	<p>sec. cor. marked $\frac{1}{2}$ on W. face, from which,</p> <p>A balm, 10 ins. diam., bears N.10°E., 33 lks. dist., marked $\frac{1}{4}$ S B T; and</p> <p>A balm, 14 ins. diam., bears S.20°W., 96 lks. dist., marked $\frac{1}{4}$ S B T.</p>	
41.50	Wagon road, course E. and W.	
43.25	O. R. and N. railroad, E. and W.	
44.00	Wagon road, course W.	
52.00	Touch the river Umatilla.	
65.50	Umatilla River, 1.50 chs. wide, course N.W.	
72.83	Intersect Township line, 1.50 chs. East of cor. to secs. 32 and 33, T. 3 N., R. 35 E. and set a stone, 7x8x9 ins., 6 ins. in the ground, for closing cor. to secs. 4 and 5 marked C C on S. face, with 4 notches on E. and 2 on W. edges, and raised a mound of stone 2 ft. high with $4\frac{1}{2}$ ft. base over it. Pits impracticable.	
	Land, rolling.	
	Soil in bottom good, 1st rate.	
	Heavy, balm fir and pine timber. 72.80 chs.	
	Good grass.	
	From the corner to secs. 5, 6, 31 and 32 on S. bdy. of Township I run	
	North on true line between secs. 31 and 32.	
	Var. 22°30' East.	
33.50	Gulch or canyon, course N.	-400
40.00	Set a stone, 12x10x8 ins., 8 ins. in the ground, for $\frac{1}{2}$ sec. cor. marked $\frac{1}{4}$ on W. face, from which,	
	A fir, 4 ins. diam., bears East 30 lks. dist., marked $\frac{1}{4}$ S B T; and	
	A fir, 16 ins. diam., bears N.40°W., 50 lks. dist., marked $\frac{1}{4}$ S B T.	
55.00	Summit of ridge, course W.	+300
80.00	Set a stone, 9x10x12 ins., 8 ins. in the ground, for cor. to secs. 29, 30, 31 and 32 marked with 5 notches on E. and 1 on S. edges, and raised a mound of stone 2 ft.	