

Subdivisions of T. 2 N., R. 35 E.

Chains		
30.00	Summit of ridge, course N.W.	+60
34.00	Canyon, course N.W.	-60
36.30	Set a stone, 10x8x6 ins., 7 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
	Ascend.	
76.30	To cor. to secs. 29, 30, 31 and 32. Land, broken and mountainous. 76.30 chs. Pine and fir timber in canyons. Good grass. Soil, 2nd rate.	
	September 10, 1887.	
	North on true line between secs. 29 and 30. Var. $21^{\circ}30'$ East.	
20.00	Begin to descend.	
40.00	Set a stone, 16x12x8 ins., 10 ins. in the ground, for $\frac{1}{4}$ S. cor. marked $\frac{1}{4}$ on W. face, and raised a mound of stone $1\frac{1}{2}$ ft. high with $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
56.30	Canyon, course N.W.	-800
80.00	Set a stone, 12x12x6 ins., 8 ins. in the ground, for cor. to secs. 19, 20, 29 and 30, marked with 5 notches on the E. and 2 on the S. edges, and raised a mound of stone 2 ft. high with $4\frac{1}{2}$ ft. base over it. Pits impracticable.	
	Land, broken and mountainous. 80 chs. Scattering pine timber. Soil, poor, 4th rate.	
	September 10, 1887.	
	East on random between secs. 20 and 29. Var. 20° East.	
40.00	Set temp. $\frac{1}{4}$ sec. cor., and at	
80.00	Intersect N. and S. line at cor. to secs. 20, 21, 28 and 29.	