

Subdivisions of T. 2 N., R. 35 E.

Chains	North on true line between secs. 7 and 8. Var. 21°30' East.	
26.00	Canyon, N.W.	-300
40.00	Set basalt stone, 26x8x8 ins., 20 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face, and raised mound of earth and stone $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it. Pits impracticable.	
60.00	Summit ridge, N.E.	+50
80.00	Set post, 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to secs. 5, 6, 7 and 8 marked T 2 N S 5 on N.E., R 35 E S 8 on S.E., S 7 on S.W., and S 6 on N.W. faces with 5 notches on S. and E. edges. Dug pits, 18x18x12 ins., in each sec. $5\frac{1}{2}$ ft. dist., and raised mound of earth 2 ft. high and $4\frac{1}{2}$ ft. base around it. Land, rough and mountainous. 80 chs. Soil, 2nd rate. Grass good.	
	East on random between secs. 5 and 8. Var. 21° East.	
40.00	Set temporary $\frac{1}{4}$ sec. cor., and at	
80.00	Intersect N. and S. line, 42 lks. S. of cor. to secs. 4, 5, 8 and 9. Thence S. 89°42' W. on true line. Var. 19° East.	
1.50	Old graded wagon road, N.W.	
2.50	Branch, 5 lks., N.W.	-50
13.00	Top ridge, and old stage road.	+300
30.50	Gulch, dry.	-200
40.00	Set stone, 30x20x15 ins., 23 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, and raised mound of stone over it. Pits impracticable.	
60.00	Top ridge, N.	+400
71.00	Canyon, N.	-500
80.00	Cor. to secs. 5, 6, 7 and 8. Land, mountainous. 80 chs. Soil, 3rd rate. No timber.	