

## Subdivisions of T. 2 N., R. 35 E.

Chains	West on random between secs. 6 and 7. Var. 21° East.	
40.00	Set temporary $\frac{1}{4}$ sec. cor., and at . . . . .	
74.00	Intersect W. bdy. Township, 50 lks. S. of cor. to secs. 6, 7, 1 and 12. Thence S. 89° 37' East on true line. Var. same.	
9.50	Canyon, N.	-200
20.00	Summit ridge, N.	+50
26.25	Canyon, N.	-50
34.00	Set stone, 16x10x8 ins., 10 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face. Dug pits, 18x18x12 ins., E. and W. of stone $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
49.00	Summit ridge, N.	+200
74.00	Cor. to secs. 5, 6, 7 and 8. Land, mountainous. 74 chs. Soil, 1st rate. Grass good. September 12, 1887.	-100
	North between secs. 5 and 6. Var. 21° East.	
40.00	Set stone, 9x8x7 ins., 6 ins. in the ground, for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist., raised mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.	
40.66	Enters field, E. and W.	
56.00	Bluff rock, E. and W., and enter bottom.	-20
59.34	O. R. and N. R. R., E. and W.	
73.54	Intersect N. bdy. Township, 143 lks. E. of cor. to secs. 31 and 32, T. 3 N., R. 35 E., and set stone, 10x10x8 ins., 6 ins. in the ground, for closing cor. marked C C on S. face, S 5 on E. and S 6 on W. faces, with 5 notches on E. and 1 notch on W. edges, and raised mound of stone over it.	