

Subdivisions of T. 2 N., R. 35 E.

Chains

Land, rolling and bottom.
 Soil, 2nd rate.
 Brush and heavy timber, pine and balm in bottom.
 17.54 chs.

September 12, 1887.

General Description

This township is very rough and mountainous, sloping to the North. There is scattering pine, fir and tamarack timber in the South part. The foothills in the North are covered with good bunch grass. The soil is rocky, 4th rate.

Retracement of South Bdy. of T. 3 N., R. 35 E.
 Surveyed by Joseph A. Ganong under special instructions.
 Dated Nov. 4, 1922.

Note: All corners hereinafter described which are at variance with the original record of the Public Land Survey and not established by me, are restorations made by the Indian Service in making Allotment Surveys and are now the best obtainable evidence of the location of the record corner, and are here particularly described as follows: All posts are 2-inch galvanized iron pipe, $3\frac{1}{2}$ ft. long, with brass cap toggled to the post, uniformly marked 'Indian Allotment Penalty \$250 For Removal,' with blank space for the addition of appropriate marks, as section, township, and range numbers.

I commence at the cor. of secs. 34 and 35, on the S. bdy. of the Tp., in latitude $45^{\circ}46'N.$, longitude $118^{\circ}24'W.$, magnetic decl. $19^{\circ}30'E.$; which is a 2-inch iron post, firmly set, and extending 12 inches above the ground, with brass cap marked

T3N	R35E
S34	S35
1919	

Thence

S. $89^{\circ}50'W.$, retracing the S. bdy. of sec. 34.

Along gentle N. slope, through grain field.

1.70 Enter thicket, bears N. and S.

1.80 Dry draw, course N.W.

4.40 Leave thicket, bears N. and S., enter field and descend N.W. slope.