

Retracement S. Bdy. T. 3 N., R. 35 E.

Chains	
9.90	Descend over rim-rock, 70 ft. high, bears NE. and SW.
12.15	Bottom of descent, bears N.E. and SW., thence over level land on river bottom through dense undergrowth.
19.97	Intersect the E 1/16 sec. cor. on the S. bdy. of sec. 34, which is a 2-inch iron post, firmly set, extending 12 inches above ground, with a mound of stone, 2 ft. base, 1½ ft. high, N. of cor., and brass cap marked
	$\begin{array}{c} \text{T3N} \text{R35E} \\ \text{E } 1/16 \text{S34} \\ \hline 1919 \end{array}$
22.15	Road, bears NE. and SW.
22.65	Right-of-Way fence, bears N.57½°E. and S.57½°W.
23.90	Center of track, O.W. R.R.&N.R.R., bears N.57°30'E. and S.57°30'W.
25.25	Right-of-Way fence, bears N.57½°E. and S.57½°W.
27.05	Road; bears NE. and SW.
34.42	Intersect the witness cor. to the ¼ sec. cor. on the S. bdy. of sec. 34, which is a 2-inch iron post, firmly set, extending 12 inches above the ground, with a mound of stone, 2 ft. base, 1½ ft. high, E. of cor., and brass cap marked
	$\begin{array}{c} \text{T3N R35E} \\ \text{WC } \frac{1}{4} \text{ S34} \\ \hline 1919 \end{array}$
34.95	Left bank of Umatilla River, course S.70°W., thence across river.
39.94	At north edge of river on flat gravel bar subject to overflow, is point for ¼ sec. cor. as hereinafter determined. Am unable to find any evidence of the old ¼ sec. cor., set temp. cor.
	Thence across river.
44.70	Left bank of Umatilla River, course N.20°W.
54.20	Left bank of Umatilla River, 150 lks. wide, course S.W. ascend SE. slope, 45 ft. over open land.
59.50	Dry ravine, course S., ascend SE. slope, 195 ft.
70.45	Top of spur, slopes S., descend W. slope, 70 ft.
74.30	Spring branch, 1 lk. wide, in ravine, course S., ascend E. slope, 114 ft. to