

## Retracement S. Bdy. T. 3 N., R. 35 E.

Chains  
79.88 Intersect the cor. of secs. 33 and 34, which is a 2-inch iron post, firmly set in a mound of stone, with brass cap marked

T3N	R35E
S33	S34
1919	

Land, rolling and level.

Soil, rich sandy loam, 1st rate and rocky 4th rate.

Timber, scattering balm.

Undergrowth, thorn, briars and vines.

Topography of T. 2 N., R. 35 E.  
Surveyed by Currin and Noland under special contract.  
Dated May 4, 1887.

From the cor. to secs. 35 and 36 on S. bdy. of Township.

North between secs. 35 and 36.

Var. 25°E.

5.75 E. branch of Squaw creek, 10 lks. wide, course N.W.

From cor. to secs. 22, 23, 26 and 27.

N.89°55' East between secs. 23 and 26.

Var. 20°E.

2.25 Squaw creek, 15 lks. wide, course North W.

From cor. secs. 23, 24, 25 and 26.

North between secs. 23 and 24.

Var. 20°E.

40.00 To the  $\frac{1}{4}$  cor. in good condition.

46.50 Canyon, course N.W.

-1000

Allotments of T. 2 N., R. 35 E.  
Surveyed by James P. Currin under contract No. 537.  
Dated March 5, 1889.

Sec. 2

From the  $\frac{1}{4}$  sec. corner on South bdy. of sec. 35, T. 3 N., R. 35 E., which is a basalt stone, 10x12x5 ins., 8 ins. in the ground, marked  $\frac{1}{4}$  on N. face, and mound of stone over it.

I run