

Allotments of T. 2 N., R. 35 E.

Chains	<p style="text-align: center;">Sec. 2</p> <p>South on true line in sec. 2 in T. 2 N., R. 35 E.</p> <p style="text-align: center;">Var. 19°E.</p> <p>3.37 Set stone, 14x10x4 ins., 10 ins. in the ground, for 1/64 sec. corner marked 1/64 on W. face, and raised a mound of stone over it.</p> <p>Pits impracticable.</p> <p>Land, slopes to North.</p> <p>Soil, 1st rate.</p> <p>Grass and sunflowers.</p>
	<p>From the 1/16 sec. corner, 20 chains W. of the $\frac{1}{4}$ sec. corner on S. bdy. of sec. 35, T. 3 N., R. 35 E., which is a post, 3 ins. square, firmly set in the ground, marked 1/16 S on N. face, and pits, 18x18x12 ins., E. and W. of post, $5\frac{1}{2}$ ft. dist., and mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around post.</p> <p>I run</p> <p>South on true line in sec. 2, T. 2 N., R. 35 E..</p> <p style="text-align: center;">Var. 20°East.</p> <p>3.20 Set post 4 ft. long, 3 ins. square, 24 ins. in the ground, with charred stake for 1/64 and 1/32 sec. corner, marked 1/64 S. on E. and 1/32 S on W. face. Dug pits, 18x18x12 ins., N. and S. of post, $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p> <p>13.20 Set stone, 10x9x6 ins., 6 ins. in the ground, for 1/32 sec. corner, marked 1/32 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base over it.</p> <p>Land, slopes to North.</p> <p>Soil, rich.</p> <p>Grass and sunflowers.</p>
	<p>From the 1/32 sec. corner, 13.20 chs. S. of the 1/16 sec. cor., 20 chs. W. of the $\frac{1}{4}$ sec. corner on the S.</p>