

Allotments of T. 2 N., R. 35 E.

Chains

Sec. 3

Land, rolling and broken.

Grass and rocks.

Sec. 4

From the $\frac{1}{4}$ sec. corner between secs. 4 and 5, which is a stone, 12x12x14 ins., 9 ins. in the ground, marked $\frac{1}{4}$ on W. face, from which,

A balm, 10 ins. diam., bears N.10°E., 33 lks. dist., marked $\frac{1}{4}$ S B T.

A balm, 14 ins. diam., bears S.20°W., 96 lks. dist., marked $\frac{1}{4}$ S B T.

I run

South on true line between secs. 4 and 5.

Var. 21°E.

- 3.50 Foot of bluff.
- 9.00 Top of bluff.
- 10.00 Set a basalt stone, 14x8x7 ins., 10 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face, and dug pits, 18x18x12 ins., N. and S. of stone, 5 $\frac{1}{2}$ ft. dist., and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.
- 20.00 Set a basalt stone, 10x8x7 ins., 6 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5 $\frac{1}{2}$ ft. dist., and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base alongside.
- 30.00 Set basalt stone, 14x9x8 ins., 10 ins. in the ground, for 1/16 sec. corner marked 1/16 on W. face. Dug pits, 18x18x12 ins., N. and S. of stone, 5 $\frac{1}{2}$ ft. dist., and raised a mound of earth 1 $\frac{1}{2}$ ft. high, 3 $\frac{1}{2}$ ft. base over it.

Land, after leaving bluff, rolling.

Soil, 1st rate.

Grass and weeds.

†150