

Allotments of T. 2 N., R. 35 E.

Chains	Sec. 4
	<p>raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around post.</p> <p>Land, rolling.</p> <p>Soil, 1st rate.</p> <p>Good grass.</p>
	<p>From the $\frac{1}{4}$ sec. corner in the center of sec. 4</p> <p>I run</p> <p>East on true line in sec. 4.</p> <p style="text-align: center;">Var. $19^{\circ}30'E$.</p>
5.50	Gulch, course N. and brushy.
6.00	Fence, course N. and S.
10.00	<p>Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground, for $1/16$ sec. corner marked $1/16$ on the N. face. Dug pits, $18 \times 18 \times 12$ ins., E. and W. of post, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around post.</p> <p>Land, rolling.</p> <p>Soil, 1st rate.</p> <p>Grass and brush.</p>
	<p>From the $1/16$ sec. corner, 10 chs. East of $\frac{1}{4}$ sec. corner in center of sec. 4.</p> <p>Thence I run</p> <p>North on true line in sec. 4.</p> <p style="text-align: center;">Var. $19^{\circ}E$.</p> <p>Through grain field.</p>
3.50	To fence, course E. and W.
5.00	<p>Set post 3 ft. long, 3 ins. sq., 24 ins. in the ground, for $1/16$ sec. corner marked $1/16$ S on W. face. Dug pits, $18 \times 18 \times 12$ ins., E. and W. of post, $5\frac{1}{2}$ ft. dist., and raised a mound of earth $1\frac{1}{2}$ ft. high, $3\frac{1}{2}$ ft. base around post.</p> <p>Land, level.</p> <p>Soil, 1st rate.</p> <p>Grain and grass.</p>