

Allotments of T. 2 N., R. 35 E.

Chains	Sec. 5
	From the 1/32 sec. corner, 20 chs. E. and 10 chs. S. of 1/4 sec. corner between secs. 5 and 6.
	I run
	South on true line in sec. 5.
10.00	Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground, for 1/16 Sec. corner, marked 1/16 S on W. face. Dug pits, 18x18x12 ins., N. and S. of post, 5 1/2 ft. dist., and raised a mound of earth 1 1/2 ft. high, 3 1/2 ft. base around post. Grassy slope to North. Sunflowers.
	From the 1/16 sec. corner, 20 chs. N. of the corner to secs. 5, 6, 7 and 8.
	I run
	East on random line in sec. 5.
	Var. 21°E.
	Setting temporary corner at 10 chs., and at
19.90	Intersect the line at 1/16 sec. corner in sec. 5.
	Thence I run
	West on true line.
	Var. 21°E.
9.95	Set post 3 ins. square, 3 ft. long, with charred stake, 12 ins. in the ground, for 1/32 sec. corner marked 1/32 S on S. face. Dug pits, 18x18x12 ins., E. and W. of post, 5 1/2 ft. dist., raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base around post.
15.00	Summit, course N.
19.90	To the 1/16 sec. corner between secs. 5 and 6. Land, rolling and mountainous. Good grass and soil, 1st rate. Some scattering brush.
	From the corner to secs. 5, 6, 7 and 8.
	I run