

## Allotments of T. 2 N., R. 35 E.

Chains	Sec. 7
	3½ ft. base over it.
25.75	Road, course S.W.
30.00	Set stone, 12x9x6 ins., 8 ins. in the ground, for 1/32 sec. corner marked 1/32 on N. face, and raised a mound of stone over it. Pits impracticable.
	Land, rough and steep.
	Soil, 1st rate and rocky.
	Grass and scattering brush.
From the 1/32 sec. corner, 30 chs. South of ¼ sec. corner between secs. 6 and 7.	
	I run
	West on true line in sec. 7.
	Var. 23°E.
13.00	Road, course N.E.
16.00	Summit, course N.E.
20.00	Set stone, 10x8x6 ins., 6 ins. in the ground, for 1/32 sec. corner, marked 1/32 on N. face. Dug pits, 18x18x12 ins., E. and W. of stone, 5½ ft. dist., and raised a mound of earth 1½ ft. high, 3½ ft. base over it.
	Land, rough and steep.
	Soil, 1st rate.
	Grass and brush.
From the 1/32 sec. corner, 30 chs. S. and 20 chs. W. of ¼ sec. corner in the center of sec. 7.	
	Thence I run
	North on true line in sec. 7.
	Var. 23°E.
9.40	Ravine, course W.
10.00	Set stone, 15x10x8 ins., 10 ins. in the ground, for 1/32 sec. corner marked 1/32 on W. face and raised a mound of stone over it. Pits impracticable.
	Thence I run