

T. 3 N., R. 36 E. (N.bdy. T.2 N.,R. 36.)

Chains		
80.00	<p>Set post corner for sections 33, 34, 3 &amp; 4 on steep hill side facing the North, from which</p> <p>A fir 10 ins. in diam. bears N.38° E. 27 lks.</p> <p>" " 7 " " " " " N.62° W. 41 "</p> <p>" " 10 " " " " " S.43° W. 38 "</p> <p>" " 12 " " " " " S.51° E. 25 "</p> <p>This line passes over very rough, broken mountain ridges the last 10-00 chs. passes through thick timber, small growth fir, larch and pine.</p>	-250
22.50	<p>East on south boundary of section 34.</p> <p>Var. 20° 30' East.</p> <p>Creek, 10 lks. wide, course North.</p>	-300
40.00	<p>Set post corner for <math>\frac{1}{4}</math> section on steep hillside, facing the West; drove charred stake, dug pits, and raised mound as per instructions.</p>	+300
47.50	<p>Summit of ridge, course North.</p>	+150
80.00	<p>Set post corner for sections 3, 4, 35, 2 &amp; 3 on steep point of rocks; deposited marked stone and raised stone mound, as per instructions.</p> <p>This line passes over broken mountain ridges. Timber on most of the northern slopes.</p>	-80
5.75	<p>East on south boundary of section 35.</p> <p>Var. 19° East.</p> <p>Small creek, 6 lks. wide, course N.W.</p>	-75
40.00	<p>Set post corner for <math>\frac{1}{4}</math> section, from which</p> <p>A fir, 12 ins. in diam. bears S.70° East 14 lks.</p> <p>No other tree near; dug pits and raised mound, as per instructions.</p>	+350
60.00	<p>Summit of ridge, course S.W.</p> <p>Var. 21° East.</p>	+500
80.00	<p>Set basalt stone 7 x 9 x 24 on steep side hill facing the south.</p> <p>This line passes over very broken, mountain ridges, quite rocky.</p>	- 50