

Chains

From the corner of sections 34 and 35 on the south boundary of the township, I run west and carefully measure along the south boundary of sec. 34 and at 72.50 to a point 22 lks. south of corner to secs. 33 and 34, showing an error in measurement of 7.50 chains.

The post is standing and all the witness trees as described in the field notes.

I can see no way of remedy for this error. I, therefore, conclude to extend it to all the crop lines on this tier of sections to the North boundary of the Township.

Extracts from Exterior 2 N., R. 37 E.
Survey by Jacob C. Cooper, under his contract No. 397,
Dated July 1st, 1881.

Thence North bet. secs. 31 & 36.
Var. 19° 30' East.

Slight ascent through heavy timber.

5.00 Enter glade, barren table land.

17.50 Descend abruptly through dense timber and undergrowth.

20.00 Descend gradually.

40.00 Set post 3½ ft. long, 3 ins. square, 18 ins. in the ground, marked ¼ S for ¼ sec. cor. in heavy timbered bottom and dense undergrowth,

A fir, 18 ins. in diam. bears N. 40° W. 31 lks. dist.,
marked ¼ S. B. T.

A fir, 16 ins. in diam. bears N. 85° E. 45 lks. dist.,
marked ¼ S. B. T.

45.00 Ascend slightly.

50.00 Enter glade (killed a bear).

69.50 Enter fallen timber, dense undergrowth. Descend.

75.00 Ascend.

80.00 Set post 4 ft. long, 4 ins. square, 2 ft. in ground for cor. to secs. 25, 30, 31 and 36, on west side of high mountain ridge, 50 feet below summit in dense thicket, post is marked: T.2, N.S.30 on N.E.; R. 37 E. S.31 on S.E.; R 36 E.S.36 on S.W., and S.25 on N.W. faces with 1 notch on S. and 5 notches on No. edges, from which