

Field Notes of the Exterior Lines of
Township 2, N., R. 36 East, by Herman D.
Gradon, under his contract No. 452, dated
June 16, 1882.

Tp. 2 N., R. 36 E. (Part E. bdy.)

Chains	
	<p>I commence at the $\frac{1}{4}$ sec. cor. bet. secs. 25 & 30, T. 2 N. R. 36 & 37. E., which is post 3 ins. square, marked $\frac{1}{4}$S on E. & W faces, with mound of stone around post,</p> <p>I run</p> <p>North bet. secs. 25 & 30.</p> <p style="text-align: right;">Var. 20° East.</p> <p>Descend about 700 ft. to</p>
40.00	<p>Set a basalt stone 20 x 12 x 10 ins., 15 ins. in the ground for cor. to secs. 24, 25, 19 & 30, marked with 2 notches on S. and 4 notches on N. edges, from which</p> <p>A fir 6 ins. in diam. bears N. 40° E. 11 lks. dist., marked T. 2 N. R. 37 E. S. 19 B. T.</p> <p>A fir 4 ins. in diam. bears N. 60° W., 31 lks. dist., marked T 2 N R. 36 E. S. 24 B. T.</p> <p>No other tree within limits and raised a mound of stone alongside.</p> <p>Land, mountainous.</p> <p>Soil, stony, 3rd rate. Timber, fir and tamarack. Dense undergrowth of young fir and tamarack.</p>
	<p>North bet. secs. 19 & 24.</p> <p style="text-align: right;">Var. 21$\frac{1}{2}$° East.</p>
11.50	<p>Descend through brush.</p> <p>Bottom of canyon, about 250 ft. below corner.</p> <p>A creek, 6 lks. wide, runs N.W.</p>
40.00	<p>Set a basalt stone 17 x 7 x 6 ins., 11 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face, and raised a mound of stone alongside.</p>
80.00	<p>Set a basalt stone 18 x 9 x 6 ins., 12 ins. in the ground for corner to secs. 13, 24, 18 & 19, marked with 3 notches on N & S. edges, from which</p> <p>A fir 8 ins. in diam. bears N. 60° E. 21 lks. dist., marked T. 2 N. R. 37 E. S. 18 B. T.</p> <p>A pine 16 ins. in diam. bears S. 10° W. 40 lks. dist., marked T. 2 N. R. 36 E. S. 24 B. T.</p>