

Chains

A fir, 12 ins. in diam. bears N.30° W. 21 lks. dist.,
marked T 2 N.R. 36 E. S.13, B.T.

No other tree within limits and raised a mound of stone
alongside.

Land, mountainous.

Soil, stony, 3rd rate.

Timber, scattering pine, fir and tamarack. Dense under-
growth of pine, fir, tamarack and buck brush.

This line from here runs alongside of and crosses a deep
rocky canyon, almost impassable and unsurveyable. I,
therefore, discontinue the line at this point.

Subdivisions, T.2 N., R. 36 East

I commence at the cor. to secs. 1, 2, 35 & 36 on the S.
boundary which is a basalt stone 14 x 12 x 8 ins.,
marked with 1 notch on E. and 5 notches on W. edges,
with a mound of stone alongside.

Thence, I run

North bet. secs. 35 & 36.

Var. 22½° East.

Ascend.

40.00

Top of hill, about 400 ft. above sec. cor., course N.W.;
set a basalt stone 18 x 12 x 8 ins., 12 ins. in the ground
for ¼ sec. cors., marked ¼ on W. face, from which
A fir, 24 ins. diam. bears N.70° W. 123 lks. dist.,
marked ¼ S.B.T.;

no other tree within limits and raised a mound of stone
alongside.

80.00

Set a post 4 ft. long, 4 ins. square, 24 ins. in the
ground for cor. to secs. 25, 26, 35 & 36, marked T2 N.
S.25 on N.E.; R36 E. S.36 on S.E.; S.35 on S.W., and
S.26 on N.W. faces, with 1 notch on S. and E. edges,
from which