

Subdivisions, T. 2 N., R. 36 E.

Chains

Land, rough and mountainous.

Soil, sandy loam and stony, 2nd & 3rd rate.

Heavily timbered with fir and tamarack. Dense undergrowth of fir and tamarack.

North bet. secs. 23 & 24.

Var. $16\frac{1}{4}^{\circ}$ East.

Along side hill through timber.

- 40.00 Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ S on W. face, from which
- A tamarack, 6 ins. in diam. bears S. 70° E. 22 lks. dist., marked $\frac{1}{4}$ S. B. T.
- A tamarack, 6 ins. in diam. bears S. 75° W. 26 lks. dist., marked $\frac{1}{4}$ S. B. T.

- 80.00 Set a basalt stone 18 x 8 x 8 ins., 12 ins. in the ground for cor. to secs. 13, 14, 23 & 24, marked with 3 notches on S. and 1 notch on E. edges, from which
- A fir, 24 ins. in diam. bears N. 20° E. 115 lks. dist., marked T 2 N R36 E. S 13 B.T.
- A fir, 22 ins. in diam. bears N. 30° W., 120 lks. dist., marked T 2 N.R. 36 E.S. 14, B.T.;
- no other tree within limits and raised mound of stone alongside.

Land, mountainous.

Soil, sandy loam, 2nd rate.

Heavily timbered with fir and tamarack. Dense undergrowth of fir, tamarack and mountain laurel.

September 26, 1882.

East on a random line bet. secs. 13 & 24.

Var. $20\frac{1}{2}^{\circ}$ E.

Through timber.

- 40.00 Set temporary $\frac{1}{4}$ sec. cor.
- 40.50 Descend steep hill about 1200 ft. to
- 72.00 Bottom of canyon; a creek, 6 lks. wide, runs N.