

Subdivisions, T. 2 N., R. 36 E.

Chains	
	a mound of stone alongside.
60.00	Top of ridge, about 1000 ft. above gulch. Course S.W.
80.00	Set a basalt stone 18 x 10 x 4 ins., 12 ins. in the ground for cor. to secs. 26, 27, 34 and 35, marked with 1 notch on S. and 2 notches on E. edges and raised a mound of stone alongside.
	Land, mountainous.
	Soil, stony, 3rd rate.
	Timber, scattering fir and pine, with dense undergrowth of buck brush.
<hr/>	
	East on a random line bet. secs. 26 & 35.
	Var. 19° East.
	Ascend through timber.
40.00	Set temporary $\frac{1}{4}$ sec. cor.
52.50	Top of ridge, about 800 ft. above sec. cor. Course N.W.
80.38	Intersect 47 lks. N. of the cor. to secs. 25, 26, 35 & 36.
	Thence, I run
	N. 89° 40' W. on a true line bet. secs. 26 & 35.
40.19	Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground for $\frac{1}{4}$ sec. corner, marked $\frac{1}{4}$ S on N. face, from which
	A tamarack, 4 ins. in diam. bears N. 40° W. 33 lks. dist., marked $\frac{1}{4}$ S. B. T.
	A tamarack, 6 ins. in diam. bears S. 25° W. 9 lks. dist., marked $\frac{1}{4}$ S. B. T.
80.38	The cor. to secs. 26, 27, 34 & 35.
	Land, rough and mountainous.
	Soil, sandy loam and stony, 2nd & 3rd rate.
	Timber, scattering fir, pine and tamarack. Dense small growth pine, fir and tamarack and wild cherry.
<hr/>	
	North bet. secs. 26 & 27.
	Var. 19° E.