

Field Notes of Exteriors (S. boundary) of  
 T. 3 N., R. 36 E., surveyed by Curran &  
 Noland, under their Special Contract, dated  
 May 4th, 1887. (N. boundary T. 2 N., R. 36)

Chains		
	From the cor. to tps. 3 N. Rs. 35 & 36 East, I run E. on random on S. bdy. of Tp. 3 N. R 36 E. At each 40 & 80 chains, I set temp. $\frac{1}{4}$ sec. and sec. cor. At 2 miles & 30 lks. I found the cor. to secs. 32 & 33, 1.35 N. of line. From this cor., which is a post 40 x 4 x 4 ins. in a mound of stone in good order, I run	
	S. 89° 30' W. on true line on South boundary of sec. 31.	
	Var. 22° East.	
2.00	Gulch, course S.W.	-100
7.20	Intersect U. R. bdy. 20.00 chs. S. 20 W. of 37th mile post. Set a basalt stone 16 x 16 x 4 ins., 10 ins. in the ground for closing cor. to Tps. 2 & 3 N. R. 36 East Marked U. R. C. C. Raised a stone mound over it. Pits impracticable.	
15.00	Top of ridge, N.W.	+200
37.00	Gulch, course W.	-400
40.00	Set a basalt stone 10 x 8 x 8 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face. Raised a stone mound over it. Pits impracticable.	
50.00	Brook, course N.W. 2 lks.	-250
62.50	Top of ridge.	+ 50
79.50	Gulch, course N.W.	-100
80.00	Set a stone 12 x 10 x 10 ins. on a ledge of rock for cor. to secs. 31 & 32; raised a stone mound around it. Pits impracticable.	-200
	Land, mountainous 80.00 chs.	
	Soil, 3rd rate.	
	Scattering pine and fir timber. Heavy underbrush in places.	
	S. 89° 30' W. on S. bdy. sec. 31.	
	Var. 22° E.	
10.50	O. R. & N. R. R. N & S.	
20.50	Meacham Creek, course N. 60 lks.	
	Leave bottom.	