

T. 2 N., R. 36 E.

Chains		
40.00	Set a basalt stone 9 x 8 x 8 ins., 6 ins. in the ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on N. face; raised stone mound over it. Pits impracticable.	†200
65.00	Top of rocky, steep ridge.	†600
80.30	To cor. to Tps. 3 N. Rs. 35 & 36, E. Land, mountainous, 80.30 chs. Soil, rocky, 4th rate. Very little timber or grass.	
<hr/> <p>Field Notes of the Retracement of Exterior Lines of Township 2 North, Range 36 East. Survey by Charles L. Campbell, under his joint contract No. 733, dated March 22, 1901.</p> <hr/>		
	From the cor. of secs. 33 and 34 on the North bdy. of T. 2 N. R. 36 E., described heretofore, I run, West bet. secs. 4 and 33 on blank line.	
	Ascend through heavy timber, along steep N. slope of hill.	
13.90	Ravine, 150 ft. deep, course N. 60° E. Ascend steep E. slope of ridge.	
14.00	Leave heavy timber; bears N. E. and S.W.	
33.00	Top of ridge, 300 ft. above cor. bears N. 10° E., S. 10° W. Descend into deep ravine.	
38.50	Enter undergrowth, bears N. and S.	
41.00	Foot of ravine, 150 ft. deep, course N. 50° W.	
41.06	Intersect old $\frac{1}{4}$ sec. cor., which is a stake badly decayed and marks nearly all obliterated.	
	I reestablish this old $\frac{1}{4}$ sec. cor. in the same place as follows:	
	Set an iron stone, 15 x 12 x 6 ins., 10 ins. in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on the N. face. Raise a mound of stone, 2 ft. base, 1 $\frac{1}{2}$ ft. high N. of the cor. Pits impracticable.	
	Ascend E. slope of ridge.	
42.25	Enter scattering timber, bears N. and S. 30° East.	
57.50	Leave scattering timber and undergrowth, bears N and S.	