

T. 2 N., R. 37, East.

Chains	Over level bench:
60.00	Ascend gradually through heavy timber and dense undergrowth, bears E. and N. 30° W.
79.90	Intersect the closing corner of secs. 30 and 31, established by me July 16, 1901.
80.70	Intersect the old corner of secs. 25 and 36 described heretofore.
	Land, mountainous.
	Soil, loam and stony; 1st, 2nd and 3rd rate.
	Timber, pine, fir, tamarack and spruce.
	Undergrowth, mountain laurel, yew, vine maple and huckleberry.
	Mountainous land 80.70 chains.
	August 12, 1901.
	August 13: At 7 ^h 50 ^m A. M. l. m. t., I set off 45° 37' on the lat. arc, 14° 48' N. on the decl. arc, and determine a true meridian with the solar at the cor. of secs. 25 and 36.
	Thence, I run
	N. 0° 12' W. bet. secs. 25 and 30 on old township line.
	Descend along W. slope through heavy timber and dense undergrowth.
4.00	Foot of hill, 50 ft. below old sec. cor.
	Spring branch, 2 lks. wide, course N.E.
	Ascend hill, bears N.E., S. W.
21.00	Leave timber and undergrowth, bears N.E., S.W.
25.00	Top of rise, 100 ft. above creek, bears N. 30° W., S. 30° W.
40.37	Intersect the old $\frac{1}{4}$ sec. cor. which is a post set loosely in a mound of stone, marked and witnessed as described by the Surveyor General. I reset the post in a mound of stone and take new bearing tree since the old bearing tree is dead. I mark
	A fir, 16 ins. in diam., bears S. 44° E., 216 lks. dist., marked $\frac{1}{4}$ S.30, B. T.