

Subdivisions, T. 2 N., R. 36 E.

Chains	
	Ascend S. slope of high ridge.
49.00	Leave scattering timber, bears E. and W.
78.00	More gradual ascent.
80.25	Summit of divide, 800 ft. above creek, bears N. 30° W., S. 30° E.
	Descend gradually, N. slope of ridge.
81.10	The cor. of secs. 10, 11, 14 and 15.
	Land, mountainous.
	Soil, rich loam and stony; 1st and 4th rate.
	Timber, pine, fir, alder, spruce and tamarack.
	Mountainous land, 81.10 chs.
	At this sec. cor., I set off 23° 20' N. on the decl. arc, and at 12 ^h 03 ^m P. M.; l. m. t., observe the sun on the meridian, the resulting latitude is 45° 40', which is about 0.3' greater than the proper lat.
	N. 0° 02' W. bet. secs. 10 and 11.
	Descend steep N. slope of ridge into canyon.
0.65	Pack trail, bears N. 60° W., S. 60° E.
2.25	Enter scattering timber and dense willow thickets, bear E. and N. 60° W.
35.75	Foot of hill 500 ft. below top of ridge.
	Dry bed of stream, Rine Creek, 10 lks. wide, course N. 20° W. Water sinks above.
	Ascend across small rise.
36.00	Leave willow thickets, bear N.W., S.E.
40.00	Set ironstone, 15 x 12 x 8 ins., 10 ins. in ground for $\frac{1}{4}$ sec. cor., marked $\frac{1}{4}$ on W. face, from which A pine, 18 ins. diam., bears N. 55° E., 132 lks. dist., marked $\frac{1}{4}$ S. 11, B.T. A fir, 10 ins. in diam., bears S. 1-1/3° W., 200 lks. dist., marked $\frac{1}{4}$ S. 10, B.T.
41.50	Top of rise, bears S. 60° W. Descend.
43.00	Branch of Rine Creek, 4 lks. wide, swift current, course S. 40° W.