

South Boundary of T. 3 N., R. 37 E.

Chains	A fir, 8 ins. diam., bears N.42°E., 7 lks. dist. " " 10 " " " S.40°W., 47 " "	
60.75	Brook, 10 lks. wide, course S.E.	-300
62.00	Leave timber, course S.E. and N.W.	
80.00	Set basalt stone, 14x10x5, on East side of mountain for corner to sections 32, 33, 4 and 5, from which, A pine, 8 ins. diam., bears S.72°W., 70 lks. dist. A fir, 8 ins. diam., bears N.20°W., 120 lks. dist. No other trees. Land, surface mountainous. Soil, third rate. Good timber on West 62 chains, remainder scattering fir, pine and tamarack. April, 14, 1879.	
	East along the South boundary of sec. 33. Var. 28°30' East.	
24.00	South branch of Umatilla river, 50 lks. wide, course N.E.	-200
27.00	Creek, 20 lks. wide, course N.W.	
28.00	Toll road from Pendleton to LaGrande, course S.E. and N.W.	
40.00	Set stone, 18x8x7, on S.W. hillside for $\frac{1}{4}$ sec. cor. No trees up along South side of ridge.	+150
80.00	Set stone basalt, 18x12x10, on South face of ridge, for corner to sections 33, 34, 3 and 4. Drove stake and raised mounds of stone around stone and stake in lieu of pits. (No trees). Land, surface mountainous. Soil, 3rd rate. Scattering pine and fir timber on West 30 chs., remainder open. Good grass.	+300
	East along the South Boundary of section 34. Var. 19°45' East.	
32.00	In ravine and up ravine.	+30
40.00	Set stone basalt, 20x12x4, on North side of ravine, for $\frac{1}{4}$ sec. cor. No trees.	+50