

West Boundary of T. 2 N., R. 38 E.

Chains	Ascend thru open timber.
62.00	Summit of ridge, 500 ft. above road just passed. Parallel with summit of ridge.
80.00	Marked a fir tree, 18 ins. diam., for cor. to secs. 19, 24, 25 and 30, on West summit of ridge. T 2 N S 19 on N.E., R 38 E S 30 on S.E., R 37 E S 25 on S.W. and S 24 on N.W. faces. <p>A pine, 20 ins. diam., bears S.36°E., 4 lks. dist., marked T 2 R 38 E S 30 B T.</p> <p>A fir, 12 ins. diam., bears N.37°E., 17 lks. dist., marked T 2 N R 38 E S 19 B T.</p> <p>A fir, 26 ins. diam., bears N.40°W., 96 lks. dist., marked T 2 N R 37 E S 24 B T.</p> <p>A fir, 14 ins. diam., bears S.48°W., 63 lks. dist., marked T 2 N R 37 E S 25 B T.</p> <p>Land, rough, mountainous and broken. Soil, gravelly, 4th rate. Timber, fir, pine and tamarack.</p>
	North between secs. 19 and 24. <p style="text-align: center;">Var. 21°45'E.</p> Descend gradually along West side of mountain in heavy timber.
34.35	Dry creek, course S.10°W.; ascend slightly.
40.00	Set post 50 ft. above creek on hillside. Post, 3½ ft. long, 3 ins. square, 1½ ft. in ground, marked ¼ S on E. and West faces, for ¼ sec. cor. <p>A fir, 22 ins. diam., bears S.48°E., 10 lks. dist., marked ¼ S B T.</p> <p>A fir, 13 ins. diam., bears S.43°W., 26 lks. dist., marked ¼ S B T.</p> <p style="text-align: center;">Var. 23°E.</p>
60.00	Enter young pine timber and undergrowth. Descend.
66.00	Ascend.
67.50	Enter glade.