

## West Boundary of T. 2 N., R. 38 E.

Chains	
42.00	Summit, 900 ft. above bottom of ravine just passed.
43.00	Enter timber and undergrowth.
44.00	Descend through timber, mostly dead and fallen.
75.50	Creek, 5 lks. wide, course West. Ascend abruptly thru medium timber and undergrowth.
80.00	Set post on South side of steep mountain in open pine timber, 300 ft. above creek, post marked for cor. to secs. 1, 6, 7 and 12., T 2 N S 6 on N.E., R 38 E S 7 on S.E., R 37 E S 12 on S.W. and S 1 on N.W. faces with 5 notches on S. and 1 notch on North faces.
	A double pine, 30 ins. diam., bears N.72°W., 90 lks. dist., marked T 2 N R 37 E S 1 B T.
	A fir, 28 ins. diam., bears N.26°E., 125 lks. dist., marked T 2 N R 38 E S 6 B T.
	A fir, 16 ins. diam., bears S.68°E., 150 lks. dist., marked T 2 N R 38 E S 7 B T.
	Land, rough and mountainous and broken.
	Soil, gravelly, 4th rate.
	Timber, fir, pine, spruce and tamarack.
	North between secs. 1 and 6.
	Var. 20°45'E.
	Ascend abruptly.
7.50	Summit of ridge, course E. and West. Descend gradually.
10.00	Soil, 1st quality, level, nearly gently sloping North.
40.00	Set post 3½ ft. long, 3 ins. square, 1½ ft. in ground, marked ¼ S on E. and W. faces for ¼ sec. cor. in burned and fallen timber and rank weeds.
	A fir, 26 ins. diam., bears N.41°E., 31 lks. dist., marked ¼ S B T.
	A fir, 20 ins. diam., bears S.55°E., 104 lks. dist., marked ¼ S B T.
	Descend slightly.
48.00	Spring branch, course N.W.
61.00	Spring branch, course N.W.
78.00	Spring branch, course W., over nearly level land. Set