

West Boundary of T. 2 N., R. 38 E.

Chains
80.00

post in burnt and fallen timber and rank weeds. I made thorough search for the corner previously established to Tps. 2 and 3 N., Rs. 37 and 38 E. but could not find it, so I set the above post, which is a maple, 5 ins. square, 4 ft. long, 2 ft. in the ground, as a closing corner to Township 2 North, Rs. 37 and 38 E. marked C C T 2 N on S., R 38 E S 6 on E. and R. 37 E S 1 on W. faces with 6 notches on S. E. and W. faces,

A fir, 32 ins. diam., bears S.54°W., 42 lks. dist., marked T 2 N R 37 E S 1 B T.

A fir, 8 ins. diam., bears S.34°E., 39 lks. dist., marked T 2 N R 38 E S 6 B T.

Land, gently sloping to the North.

Soil, black, rich loam, 1st rate, covered with rank weeds.

Timber, fir, spruce and tamarack, most dead and fallen from recent fires.

Oct. 5, 1881.

Resurvey of South Boundary of T. 3 N., R. 37 East.
Surveyed by William E. Campbell, joint contract No. 718.
Dated May 1, 1900.

Preliminary to commencing the subdivisions of this Township I run West on S. bdy. of sec. 36, at 40.00 chs. fail to find any trace of the $\frac{1}{4}$ sec. cor. Set temp. $\frac{1}{4}$ sec. cor., and at 80.00 chs. intersect cor. of secs. 35 and 36. Therefore, in accordance with my special written instructions and the Manual, after retracement and resurvey of E. bdy. I resurvey this S. bdy. of sec. 36 as follows:

July 28: At 9.20 a.m., l.m.t., I set off 45°41'30" on the lat. arc; 19°00'N. on the decl. arc. and determine a true meridian by the solar at the S.E. cor. of Tp. already described.

Thence I run

West on S. bdy. of sec. 36.