

## Resurvey of South Bdy. of T. 3 N., R. 37 E.

Chains	
	<p>The old cor. of secs. 35 and 36, a broken basalt stone, marked and witnessed as described by the surveyor general, bears W. 1 ch. 25 lks. dist. I destroy all traces of this old sec. cor.</p> <p>Land, nearly level and mountainous.</p> <p>Soil, part is arable, gravelly, loam and stone, 2nd, 3rd, and 4th rates.</p> <p>Heavily timbered with pine, fir and tamarack, 10.50 chs.</p> <p>Densely overgrown with pine, fir, tamarack, alder, willow, cascara, fern, pine grass, huckleberry and bunchgrass. 31.00 chs.</p> <p>Good pasture land.</p> <p>Mountainous, heavily timbered or lands densely covered with undergrowth, 72.50 chs.</p> <p style="text-align: right;">July 28, 1900.</p>
	<p>Note: In retracing S. bdy. of sec. 35, for the purpose of reestablishing cors. thereon common to two sections, I discovered it to be defective in alinement as follows:</p> <p>August 2: I run West on S. bdy. of sec. 35 and at 40.00 chs. set temp. <math>\frac{1}{4}</math> sec. cor; at 41.06 chs. the old <math>\frac{1}{4}</math> sec. cor. bears N.50 lks. dist., at 80.00 chs. set temp. cor. at secs. 34 and 35; at 80.61 chs. the old cor. of secs. 34 and 35 bears N.82 lks. dist.; therefore, I continue my line West and at 5 miles, no chs. and 34 lks., fall 1 ch. 84 lks. S. of the cor. of T. 3 N., Rs. 36 and 37 E. and as these Townships have not been subdivided I resurvey this portion of the S. bdy. as follows:</p> <p>August 6: At 7h 30m a.m., l.m.t., I set off <math>45^{\circ}41'30''</math> on the lat. arc., <math>16^{\circ}45'N.</math> on the decl. arc. and determine a true meridian by the solar at the cor. of secs. 35 and 36.</p> <p>Thence I run</p> <p>N.89<math>^{\circ}</math>44'W., on a true line S. bdy. of sec. 35.</p> <p>Descending steep, stony hill, through heavy timber and undergrowth, bears N.30<math>^{\circ}</math>W. and S.30<math>^{\circ}</math>E.</p>